GRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer Dasarahalli Division,

SCHEDULE-B

Name OF Work: Improvement to Ashwathakatte Near Mallikarjuna Swamy temple Mallasandra Ward No.13 Shettihalli Sub Division

Name of the Contractor: Sri.Manojnaik

Sl.No	Description of work	Unit	Qty	Sanctioned Approved	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	KSRRB 2-2.2. Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches1.5m and above in width,in hard soil not exciding 1.5 m. depth incluiding dressing the bottom and sides of pits and trenches,stacking the excavated soil clear from edges of excavation with lead upto 50m.after breakingof clods complete as per specifications, specation. No. KBS 2.1(b)/2:3.5(I.tm No.2.4, p.No.5, SR:2016-17)	Cum	65.83	405.64	Rupees Four Hundred Five and Paise Six Four Only
2	Providing and laying in position plain cement concrete of mix 1:3:6 with opc cement @220kgs with 20 mm and down size graded granite metal course aggregate @0.84cum and fine aggregates @0.56 cum machine mixed,laid in layers not exceeding 15cms thick well compacted in foundation,plinth and cills including cost of all materials,labour,HOM OF machinary, curing complete as per specification (Pg No-12.Item No.4.2)	Cum	21.21	5449.68	Rupees Five Thousand four Hundred Fourty nine and Paise Six eight Only
3	Providing and Laying in position reinforced cement concrete of design mix M25 with OPC cement @ 320Kgs with 20mm and down size graded granite metal course aggregate @ 0.878cum and fine aggregate @ 0.459cum, with superplastisiser @ 3ltr confirming to IS 9103-1999 Reaffirming 2008, machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground level for roof slab, stairecase, lintels, retaining wall , return wall, wall (any thickness) including attahed plasters, column , piers, abutmentspillers, posts, struts, buttresses, string or laceing courses, parapets, coping, bed blocks, anchor hooks plain window cill, fillets, etc.., including cost of all materials, Labours, HOM of Machineries, curing complete as per specification. Complete as per the direction of Engineer-in-Charge of the work	Cum	38.56	6718.68	Rupees Six Thousand seven Hundred Eighteen and Paise Six eight Only

Scanned by CamScanner

4	Filling Available excavated earth(excluding rock) inside cum of foundation upto plinth in layers not exceeding 20cm in depth compacting each deposited layer by ramming after watering with lead upto 50mtr and lift upto 1.5mtr including cost of all labour etc complete as per specification. specificatrion	Cum	31.40	137.16	Rupees One Hundred Thirty Seven and Paise One Six Only
5	KSRRB : Providing and constructing granite / trap / basalt size stone masonry in Foundation with cement mortar 1 :8, stone hammered dressed in courses not less than 20cms high, bond stones at 2 m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 (Page No-23, Item No-5.6 SR2016-17)	Cum	1.44	4359.96	Rupees Four Thousand three Hundred fifty nine and Paise ninty Six Only
6	Providing and Removing centering and shuttering, strutting proping etc. and removal of form work for foundations footings bases of columns for mass concrete including cost of all materials labour complete as per specifications. Specification No. KBS 4.3.2(Item No.4.28 Page No.15) SR 2016-17.	Sqm	213.76	249.48	Rupees Two Hundred Forty Nine and Paise Fourty Eight Only
7	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3, TMT bars Fe 500. Page No. 17/ Item No. 4.46.2/ PWD SR 2016-17	Tonnes	3.08	65455.56	Rupees Sixty Five Thousand Four Hundred Fifty Five and Paise Ninety Six Only
8	KSRB 2.5: Eartwork excavation in all soil deposits and filling sides of foundation upto plinth in layer not exceding 20cms. In depth, compacting each deposited layer by ramming after watering with all lead and lift including cost of all labour complete as per specifications,specification.(I.No.2.12, P.No.-06, Sr:2016-17)	Cum	139.78	374.32	Rupees Three Hundred Seventy Foure and Paise Thirty Two Only

Scanned by CamScanner

9	Providing and Fixing for flooring 20mm thick gang saw water cut sadarahalli gray granite in CM 1:4 propotion, cut to required shape, pattern with paper joints, finished with cement mortor using white cement and colour pigments to match the colour pigments to match the colour of slab making through jointing with sealant, groves in joints including cost of curring - Minimum width of 1200mm.,complete as per specification.KSRB 14.61.1	Sqm	80.44	1984.00	Rupees One Thousand Nine Hundred Eighty Four Onlyly
10	Providing and fixing 20mm thick gang saw water cut LAKARED granite for cladding in CM 1:4 cut to required shape, pattern woth paper joints, finished with cement mortar using, white cement colour pigments to match the colour of slab making through jointing with sealant, grooves in joints including cost of curing etc., complete including cost and conveyance of all materials, mortar labour for all items of work, HOM of equipment etc., complete as per specification.(I. No.-14.60. P. No.-109, SR 2016-17)	Sqm	44.69	3990.60	Rupees Three Thousand Nine Hundred Ninty and Paise Sixty Only
11	Providing and fixing 304 grade stainless steel hand rails of 14 guage pipes for Ramps staircase made out of stainless steel hollow piupes using 50 mm dia for verticals@ 1.60 mts c/c fixed to the ramps or steps by drilling with bolts and 100mm dia M S base plates 10mm guage for fixing of vertical pipes 4 Nos ancher bolts& 40 mm dia pipes fixed horizontally for 2 rows top one pipe fixed with vertical pipes another one fdixed with elbows and 25 mm dia pipes are fixed horizontally for 2 rows below top measure @ equal intervels including cutting welding bending wherever necessary with suitable caps @ tops bottoms & corners finishing with mat /shining etc complete including cost and conveyance of all materials labour for all items of work HOM of equipment with all lead and lift loading and unloading transportation charges and all other incidental charges etc complete as per specification and direction of the Engineer incharge of the work Ramps of staircase for physically challanged (P No-43 ,I No-7.39 SR2016-17)	Sqm	39.00	6286.68	Rupees Six Thousand Two Hundred Eighty Six and Paise Sixty eight Only
12	Providing full nosing for 20mm thick granite slab using required machinary including cost and conveyance of all materials; labour for all items of works H O M of equipment etc; complete as per specification (I No-14.55 ; P-No-108 S R 2016-17)	Mtr	64.10	257.04	Rupees Two Hundred Fifty Seven and Paise Zero Four Only

Scanned by CamScanner

13	Providing granite slabs of selected quality roughly dresses having a size of 10 cms thick and fixing in cement mortor (1:6) including fixing curing etc.,complete as per specifications.	Sqm	52.17	825.82	Rupees Eight Hundred Twenty Five and Paise Eighty Two Only
14	KSRB 5-8.2 : Providing two line dressing to granite stone slab / granite stone masonry as per specifications KBS 5.1.13	Sqm	52.17	963.63	RupeesNine Hundred Sixty Three and Paise Sixty Three Only
15	Providing And Constructing Mantapa using Sadarahallli Granite stones of size of 0.40x0.40x2.3 measurment for four numbers pillers and four numbers of beams of size 0.20x0.30x2.75 mtr and with granite slab roof of 4.30mtrx3.00mtrx0.15thick including cost of all loading and unloading and the lead for bringing the stone to the workspot including cost of all carving work dressing polishing and pinishing and insatalling at woork site etc.. complete	No	1.00	437441.07	Rupees Four Lackh Thirty Seven Thousand Four Hundred Fourty One and Paise Zero Seven Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Scanned by CamScanner